

HILLSIDE EROSION RESTORATION

3000 CAMPUS HILL DR,
LIVERMORE, CA

LEGEND


EXISTING	PROPOSED
SAWCUT AND CONFORM LINE	---
RETAINING WALL	=====
A.C. PAVEMENT	=====
CONC. VALLEY GUTTER	=====
CONC. SIDEWALK OR PAD	=====
6" CURB & GUTTER	=====
EDGE OF A.C. PAVEMENT	=====
6" VERTICAL CURB	=====
CENTER LINE	=====
SANITARY SEWER MAIN	8" SS
STORM DRAIN MAIN	12" SD
PERFORATED PIPE	6" P
WATER MAIN	6" W
FIRE WATER MAIN	6" FW
DOMESTIC WATER MAIN	6" DW
CHILLED WATER MAIN	6" CHW
IRRIGATION LINE	2" IRR
HOT WATER SUPPLY & RETURN	HWS-HWR
STEAM LINE	ST
TRENCH DRAIN	-----
CONDENSATE RETURN	CR
METAL BEAM GUARD RAIL	=====
SILT FENCE	-----
FLOW LINE	-----
CHAIN LINK FENCE	-----
GAS MAIN	G
ELECTRIC AND SIGNAL DUCT BANK	E
OVERHEAD ELECTRIC LINE	OHE
UNDERGROUND ELECTRIC LINE	UGE
STREET LIGHT CONDUIT	SL
CONTOUR ELEVATION LINE	85
SPOT ELEVATION	x 95.94
DIRECTION OF SLOPE	2:1 1X
GAS METER	GM
GAS VALVE	GV
WATER METER	WM
WATER VALVE	WV
FIRE HYDRANT	PH
BACK FLOW PREVENTOR	PFP
POST INDICATOR VALVE	PIV
FIRE DEPARTMENT CONNECTION	FD
WATER LINE TEE	WT
CAP AND PLUG END	CP
AIR RELEASE VALVE	ARV
SIGN	S
ACCESSIBLE RAMP	AR
CONCRETE THRUST BLOCK	CTB
REDUCER	R
SANITARY SEWER MANHOLE	SSM
SANITARY SEWER CLEANOUT	SSCO
STORM DRAIN MANHOLE	SDM
STORMCEPTOR	ST
STORM DRAIN AREA DRAIN	SDAD
STORM DRAIN CATCH BASIN	SDCB
STORM DRAIN CURB INLET	SDCI
STORM DRAIN CLEANOUT	SDCO
ELECTROLYZER	EL
JOINT POLE	JP
OVERLAND RELEASE	OR
CONSTRUCTION DETAIL REFERENCE	75
	CS.00

ABBREVIATIONS

AB	AGGREGATE BASE
AC	ASPHALT CONCRETE
AD	AREA DRAIN
ADA	AMERICANS WITH DISABILITIES ACT
ASB	AGGREGATE SUBBASE
BC	BEGINNING OF CURVE
BFP	BACK FLOW PREVENTOR
BLDC	BUILDING CORNER
BLDG	BUILDING
BOD	BOTTOM OF DOCK
BOL	BOLLARD
BOS	BOTTOM OF STEP
BOW	FG @ BOTTOM OF WALL
BVC	BEIGN VERTICAL CURVE
BW	BACK OF WALL
C	CONCRETE OR CIVIL
C&G	CURB AND GUTTER
CB	CATCH BASIN
CI	CURB INLET
CIP	CAST IRON PIPE
CL	CENTER LINE OR CLASS
CM	CORRUGATED METAL PIPE
CO	CLEANOUT
CONC	CONCRETE
CONST	CONSTRUCTION OR CONSTRUCT
CY	CUBIC YARD
DCDA	DOUBLE CHECK DETECTOR ASSEMBLY
DI	DROP INLET
DIP	DUCTILE IRON PIPE
DM	DOMESTIC WATER
DW	DOMESTIC WATER
DWS	DRAINING
E	EAST
EC	END OF CURVE
EP	EDGE OF PAVEMENT
ER	END OF RETURN
EVC	END VERTICAL CURVE
ELEV	ELEVATION
EX, EXST.	EXISTING
FC	FACE OF CURB
FDC	FIRE DEPARTMENT CONNECTION
FF	FINISHED FLOOR
FG	FINISHED GRADE
FH	FIRE HYDRANT
FL	FLOW LINE
FOUND	FOUNDATION
FS	FINISHED SURFACE
FT	FOOT
FW	FIRE WATER
G	GROUND ELEVATION
GB	GRADE BREAK
GV	GATE VALVE
HCR	ACCESSIBLE RAMP
HP	HIGH POINT
INV	INVERT ELEVATION
JP	JOINT POLE
JT	JUMP TRENCH
LIP	LIP OF GUTTER
LP	LOW POINT
LSA	LANDSCAPE ARCHITECT
MAX	MAXIMUM
MEP	MECHANICAL/ELECTRICAL/PLUMBING
MH	MANHOLE
MIN	MINIMUM
MVC	MIDPOINT OF VERTICAL CURVE
MON	MONUMENT
N	NORTH
N.C.	NOT IN CONTRACT
NO	NUMBER
NTS	NOT TO SCALE
P	PAVEMENT ELEVATION
PCC	PORTLAND CEMENT CONCRETE / POINT OF CONTINUOUS CURVATURE
PIV	POST INDICATOR VALVE
PL	PROPERTY LINE
PMH	POWER MANHOLE
POC	POINT ON CURVE
PP	POWER POLE
PRC	POINT OF REVERSE CURVATURE
PVC	POLYVINYL CHLORIDE PIPE
R	RADIUS
RC	RELATIVE COMPACTION
RCP	REINFORCED CONCRETE PIPE
RPPA	REDUCED PRESSURE PRINCIPLE ASSEMBLY
R/W	RIGHT OF WAY
S	SLOPE OR SOUTH
S.A.D.	SEE ARCHITECTURAL DRAWINGS
SD	SEDIMENT BASIN
SD	STORM DRAIN
S.E.D.	SEE ELECTRICAL DRAWINGS
SG	SILT FENCE
SG	SUBGRADE
S.L.D.	SEE LANDSCAPE DRAWINGS
S.M.D.	SEE MECHANICAL DRAWINGS
SMH	SIGNAL MANHOLE
S.P.D.	SEE PLUMBING DRAWINGS
SS	SANITARY SEWER
STA	STATION
STD	STANDARD
S/W	SIDEWALK
TD	TOP OF CURB
TD	TRENCH DRAIN
TD	TOP OF DOCK
TOE	TOE OF SLOPE
TOS	TOP OF STAIR
TOW	TOE @ TOP OF WALL
TS	TOP OF SLAB
TYP	TYPICAL
UNO	UNLESS OTHERWISE NOTED
UG	UNDERGROUND
UC	UNDERGROUND
V/C	VERTICAL CURVE
W	WATER
WV	WATER VALVE
WV	WATER VALVE
WVF	WELDED WIRE FABRIC
W/	WITH



VICINITY MAP



KEY MAP

CONSTRUCTION NOTES

- ALL ON-SITE CONSTRUCTION MATERIAL AND METHODS SHALL COMPLY WITH THE LATEST EDITION OF THE AMERICAN NATIONAL STANDARDS INSTITUTE, COUNTY OF ALAMEDA STANDARD PLANS AND SPECIFICATIONS, AMERICAN CONCRETE INSTITUTE, AMERICAN SOCIETY FOR TESTING AND MATERIALS, STATE OF CALIFORNIA CONSTRUCTION SAFETY ORDERS, CALIFORNIA CODE OF REGULATIONS, CITY OF LIVERMORE STANDARD PLANS & SPECIFICATIONS, AND THE LATEST CALTRANS STANDARD SPECIFICATIONS (2015).
- CONTRACTOR SHALL POST ON THE SITE, EMERGENCY TELEPHONE NUMBERS FOR AMBULANCE, POLICE, AND FIRE DEPARTMENTS.
- CONTRACTOR SHALL NOTIFY ALL PUBLIC OR PRIVATE UTILITY OWNERS 48 HOURS PRIOR TO COMMENCEMENT OF WORK ADJACENT TO THE CAMPUS FROM COLLIER CANYON ROAD.
- UTILITIES AND UNDERGROUND FACILITIES INDICATED ARE FOR INFORMATION ONLY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY THE LOCATION AND DEPTH WITH THE APPROPRIATE AGENCIES. NEITHER THE OWNER NOR THE CITY NOR THE DESIGN PROFESSIONAL ASSUMES RESPONSIBILITY THAT THE UTILITIES AND UNDERGROUND FACILITIES INDICATED WILL BE THE UTILITIES AND UNDERGROUND FACILITIES ENCOUNTERED.
- IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO IDENTIFY, LOCATE AND MARK, AND PROTECT ALL UNDERGROUND FACILITIES. CONTRACTOR TO CONTACT DISTRICT FORTY-EIGHT (48) HOURS PRIOR TO BEGINNING WORK.
- THE CONTRACTOR SHALL HIRE A STREET CLEANING CONTRACTOR TO CLEAN UP DIRT AND DEBRIS FROM CITY STREETS AND CAMPUS STREETS AND PARKING LOT THAT ARE ATTRIBUTABLE TO THE DEVELOPMENT'S CONSTRUCTION ACTIVITIES.
- ALL GRADING SHALL BE PERFORMED IN SUCH A MANNER AS TO COMPLY WITH THE STANDARDS ESTABLISHED BY THE AIR QUALITY MAINTENANCE DISTRICT FOR AIRBORNE PARTICULATES (DUSTS).
- ALL GRADING SHALL CONFORM TO APPROVED SPECIFICATIONS PRESENTED HEREON OR ATTACHED HERETO.
- ALL MATERIALS, REQUIRED FOR THE COMPLETE EXECUTION OF THE PROJECT, SHALL BE FURNISHED AND INSTALLED BY THE CONTRACTOR UNLESS OTHERWISE NOTED.
- THE CONTRACTOR SHALL PROVIDE ALL LIGHTS, SIGNS, BARRICADES, FLAGMEN OR OTHER DEVICES NECESSARY TO PROVIDE FOR PUBLIC SAFETY DURING THE CONSTRUCTION PERIOD.
- THE CONTRACTOR SHALL BE RESPONSIBLE TO REPAIR OR REPLACE ANY EXISTING IMPROVEMENTS OF UNDERGROUND AND ABOVE GROUND FACILITIES DAMAGED DURING THE CONSTRUCTION PERIOD, INCLUDING BUT NOT LIMITED TO FLAT WORK, SITE WORK, AND LANDSCAPING.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL ENCROACHMENT, EXCAVATION, CONCRETE, ELECTRICAL, PLUMBING, ETC. PERMITS NECESSARY PRIOR TO BEGINNING CONSTRUCTION FOR ANY WORK.
- THE CONTRACTOR SHALL HAVE A SUPERINTENDENT OR REPRESENTATIVE ON SITE AT ALL TIMES DURING CONSTRUCTION.
- STORAGE OF CONSTRUCTION MATERIAL AND EQUIPMENT ON CITY AND CAMPUS STREETS WILL NOT BE PERMITTED.
- CONSTRUCTION EQUIPMENT SHALL BE PROPERLY MUFFLED. UNNECESSARY IDLING OF GRADING CONSTRUCTION EQUIPMENT IS PROHIBITED.
- CONSTRUCTION EQUIPMENT, TOOLS, ETC. SHALL NOT BE CLEANED OR RINSED INTO A STREET, GUTTER OR STORM DRAIN.
- A CONTAINED AND COVERED AREA ON-SITE SHALL BE USED FOR STORAGE OF CEMENT BAGS, PAINTS, FLAMMABLE, OILS, FERTILIZERS, PESTICIDES, OR ANY OTHER MATERIALS THAT HAVE POTENTIAL FOR BEING DISCHARGED TO THE STORM DRAIN SYSTEM BY WIND OR IN THE EVENT OF A MATERIAL SPLASH.
- ALL CONSTRUCTION DEBRIS SHALL BE GATHERED ON A DAILY BASIS AND PLACED IN A DUMPSTER PROVIDED BY THE CONTRACTOR WHICH IS EMPTIED OR REMOVED WEEKLY. WHEN FEASIBLE, TARPS SHALL BE USED ON THE GROUND TO COLLECT FALLEN DEBRIS OR SPATTERS THAT COULD CONTRIBUTE TO STORMWATER POLLUTION.
- ANY TEMPORARY ON-SITE CONSTRUCTION PILES SHALL BE SECURELY COVERED WITH A TARP OR OTHER DEVICE TO CONTAIN DEBRIS. TARP SHALL BE SECURED IN SUCH A WAY THAT PREVENTS REMOVAL OR DAMAGE OF MATERIAL DUE TO ENVIRONMENTAL CONDITIONS.
- CONCRETE TRUCKS AND CONCRETE FINISHING OPERATIONS SHALL NOT DISCHARGE WASH WATER INTO THE STREET GUTTERS OR DRAINS.
- UNLESS OTHERWISE NOTED, ALL CONCRETE SHALL BE CALTRANS CLASS 2 WITH A MINIMUM COMPRESSIVE STRENGTH OF 3000 PSI.

SURVEY NOTES

- ALL DISTANCES AND DIMENSIONS ARE SHOWN IN FEET AND DECIMALS THEREOF.
- DATES OF FIELD SURVEY: 08/09/2023.
- COORDINATES, BEARINGS, AND DISTANCES SHOWN ARE BASED ON AN ASSUMED COORDINATE SYSTEM. SEE SURVEY CONTROL TABLE BELOW FOR PROJECT COORDINATES. THE VERTICAL DATUM FOR THE SURVEY IS BASED ON LAS POSITAS COLLEGE BENCHMARK NO. 22 - 3/4" IRON PIPE WITH PLUG ON THE SOUTH SIDE OF THE LOOP ROAD, APPROX. 1100' FROM THE WEST ENTRY TO THE CAMPUS FROM COLLIER CANYON ROAD.

ELEVATION = 466.71

SURVEY CONTROL TABLE

POINT #	ELEVATION	NORTHING	EASTING	DESCRIPTION
1	544.08'	13183.80'	13290.31'	OUT X
2	538.60'	13122.23'	13795.66'	HUB & TACK
3	539.04'	13129.54'	13578.72'	HUB & TACK

GENERAL SITE NOTES

- CONTRACTOR SHALL VISIT THE SITE PRIOR TO BIDDING ON THIS WORK AND CONSIDER THE EXISTING CONDITIONS AND SITE CONSTRAINTS IN THE BID. CONTRACTOR SHALL BE IN THE POSSESSION OF AND FAMILIAR WITH ALL APPLICABLE GOVERNING AGENCIES STANDARD DETAILS AND SPECIFICATIONS PRIOR TO SUBMITTING OF A BID.
- ALL WORK ON-SITE AND IN THE PUBLIC RIGHT-OF-WAY SHALL CONFORM TO ALL APPLICABLE GOVERNING AGENCIES STANDARD DETAILS & SPECIFICATIONS.
- DAMAGE TO ANY EXISTING SITE IMPROVEMENTS, UTILITIES AND/OR SERVICES TO REMAIN SHALL BE RESPONSIBILITY OF THE CONTRACTOR. CONTRACTOR SHALL REPAIR AND/OR REPLACE IN KIND.
- CONTRACTOR AGREES THAT THEY SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT INCLUDING SAFETY OF ALL PERSONS AND PROPERTY THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS AND THAT THE CONTRACTOR SHALL DEFEND INDEMNIFY AND HOLD THE CLIENT, THE CONSULTING ENGINEER AND THE CITY HARMLESS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT, EXCEPTING FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE CLIENT OR THE CONSULTING ENGINEER.

GENERAL UTILITY NOTES

- ALL TRENCHES SHALL BE BACK FILLED PER THE GEOTECHNICAL REPORT OR UTILITY OWNERS STANDARD DETAILS AND SPECIFICATIONS.
- COMPLETE SYSTEMS: ALL UTILITY SYSTEMS ARE DELINEATED IN A SCHEMATIC MANNER ON THESE PLANS. CONTRACTOR IS TO PROVIDE ALL FITTINGS, ACCESSORIES AND WORK NECESSARY TO COMPLETE THE UTILITY SYSTEM SO THAT IT IS FULLY FUNCTIONING FOR THE PURPOSE INTENDED.
- UNDERGROUND UTILITIES OR STRUCTURES ARE SHOWN IN THEIR APPROXIMATE LOCATIONS AND EXTENT BASED UPON RECORD INFORMATION. LOCATIONS MAY NOT HAVE BEEN VERIFIED IN THE FIELD AND NO GUARANTEE IS MADE TO THE ACCURACY OR COMPLETENESS OF THE INFORMATION SHOWN. THE CLIENT, BY ACCEPTING THESE PLANS OR PROCEEDING WITH IMPROVEMENTS PURSUANT THERETO, AGREES TO ASSUME LIABILITY AND TO HOLD UNDERSIGNED HARMLESS FOR ANY DAMAGES RESULTING FROM THE EXISTENCE OF UNDERGROUND UTILITIES OR STRUCTURES NOT REPORTED TO THE UNDERSIGNED, NOT INDICATED ON THE PUBLIC RECORDS EXAMINED, LOCATED AT VARIANCE WITH THOSE REPORTED OR SHOWN ON RECORDS EXAMINED.

DISCREPANCIES

IF THERE ARE ANY DISCREPANCIES BETWEEN DIMENSIONS IN DRAWINGS AND EXISTING CONDITIONS WHICH WILL AFFECT THE WORK, THE CONTRACTOR SHALL BRING SUCH DISCREPANCIES TO THE ATTENTION OF THE ENGINEER FOR ADJUSTMENT BEFORE PROCEEDING WITH THE WORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROPER FITTING OF ALL WORK AND FOR THE COORDINATION OF ALL TRADES, SUBCONTRACTORS, AND PERSONS ENGAGED UPON THIS CONTRACT.

SOILS REPORT

PROJECT HAS BEEN BASED UPON THE GEOTECHNICAL EVALUATION & GEOLOGIC HAZARDS ASSESSMENT DEVELOPED BY THE ADJACENT VITICULTURE FACILITY PROJECT, PROVIDED IN THE NINYO & MOORE GEOTECHNICAL EXPLORATION REPORT DATED 01/14/21. SUPPLEMENTAL RECOMMENDATIONS WERE PROVIDED BY ROCKRIDGE GEOTECHNICAL. ALL WORK SHOULD BE DONE IN ACCORDANCE WITH PROJECT PLANS AND SPECIFICATIONS.

DEMOLITION NOTES

- CONTRACTOR IS TO COMPLY WITH ALL GENERAL AND STATE REQUIREMENTS INVOLVING THE REMOVAL AND DISPOSAL OF HAZARDOUS MATERIAL(S).
- CONTRACTOR'S BID IS TO INCLUDE ALL VISIBLE SURFACE AND ALL SUBSURFACE FEATURES IDENTIFIED TO BE REMOVED OR ABANDONED IN THESE DOCUMENTS.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR A SITE INSPECTION TO FULLY ACKNOWLEDGE THE EXTENT OF THE DEMOLITION WORK.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ANY AND ALL PERMITS NECESSARY FOR ENCROACHMENT, GRADING, DEMOLITION, AND DISPOSAL OF SAID MATERIALS AS REQUIRED BY PRIVATE, LOCAL AND STATE JURISDICTIONS. THE CONTRACTOR SHALL PAY ALL FEES ASSOCIATED WITH THE DEMOLITION WORK.
- BACKFILL ALL DEPRESSIONS AND TRENCHES FROM DEMOLITION TO THE SATISFACTION OF THE GEOTECHNICAL ENGINEER.
- THE CONTRACTOR SHALL MAINTAIN ALL SAFETY DEVICES, AND SHALL BE RESPONSIBLE FOR CONFORMANCE TO ALL LOCAL, STATE AND FEDERAL SAFETY AND HEALTH STANDARDS LAWS AND REGULATIONS.
- PROTECT ALL EXISTING UTILITIES IN PLACE UNLESS OTHERWISE NOTED. REPLACE ANY DAMAGED UTILITY TO REMAIN TO KEEP OPERABLE DURING CONSTRUCTION.
- ALL UTILITY SHUT DOWNS ARE TO BE AVOIDED. IF SHUT DOWNS ARE NECESSARY, CONTRACTOR TO COORDINATE SHUT DOWN WITH UTILITY OWNER WITH 48 HOUR MINIMUM NOTICE.
- SECURE ALL REQUIRE PERMITS OR CERTIFICATES FOR DEMOLITION OR DISCONTINUANCE OF UTILITIES, PRIOR TO BEGINNING THE WORK.

DUST CONTROL NOTES

- WATER TRUCKS SHALL BE PRESENT AND IN USE AT THE CONSTRUCTION SITE. ALL PORTIONS OF THE SITE, SUBJECT TO BLOWING DUST SHALL BE WATERED AS OFTEN AS DEEMED NECESSARY BY THE CLIENT/INSPECTOR IN ORDER TO INSURE PROPER CONTROL OF BLOWING DUST FOR THE DURATION OF THE PROJECT.
- ALL PUBLIC STREETS AND MEDIANS SOILED OR LITTERED DUE TO THIS CONSTRUCTION ACTIVITY SHALL BE CLEANED AND SWEEPED ON A DAILY BASIS DURING THE WORK WEEK, OR AS OFTEN AS DEEMED NECESSARY BY THE CLIENT/INSPECTOR, OR TO THE SATISFACTION OF THE CHABOT-LAS POSITAS COLLEGE DISTRICT STANDARDS.
- ALL TRUCKS HAULING SOIL, SAND, AND OTHER LOOSE MATERIALS SHALL BE COVERED WITH TARPULINS OR OTHER EFFECTIVE COVERS.
- WHEEL WASHERS SHALL BE INSTALLED AND USED TO CLEAN ALL TRUCKS AND EQUIPMENT LEAVING THE CONSTRUCTION SITE. IF WHEEL WASHERS CANNOT BE INSTALLED, TIRES OR TRACKS OF ALL TRUCKS AND EQUIPMENT SHALL BE WASHED OFF BEFORE LEAVING THE CONSTRUCTION SITE.
- THE CONTRACTOR SHALL DEMONSTRATE DUST SUPPRESSION MEASURES, SUCH AS REGULAR WATERING, WHICH SHALL BE IMPLEMENTED TO REDUCE EMISSIONS DURING CONSTRUCTION AND GRADING IN A MANNER MEETING THE APPROVAL OF THE CONSTRUCTION MANAGER. THIS SHALL ASSIST IN REDUCING SHORT-TERM IMPACTS FROM PARTICLES WHICH COULD RESULT IN NUISANCES THAT ARE PROHIBITED BY RULE 403 (FUGITIVE DUST).
- GRADING OR ANY OTHER OPERATIONS THAT CREATES DUST SHALL BE STOPPED IMMEDIATELY IF DUST AFFECTS ADJACENT PROPERTIES. THE CONTRACTOR SHALL PROVIDE SUFFICIENT DUST CONTROL FOR THE ENTIRE PROJECT SITE IN ACCORDANCE WITH THE PROJECT SWPPP (IF ONE EXISTS) OR AS APPLICABLE PER LOCAL REGULATIONS AT ALL TIMES. THE SITE SHALL BE SPRINKLERED AS NECESSARY TO PREVENT DUST NUISANCE. IN THE EVENT THAT THE CONTRACTOR NEGLECTS TO USE ADEQUATE MEASURES TO CONTROL DUST, THE CLIENT RESERVES THE RIGHT TO TAKE WHATEVER MEASURES ARE NECESSARY TO CONTROL DUST AND CHARGE THE COST TO THE CONTRACTOR.
- THE CONTRACTOR IS RESPONSIBLE FOR DUST CONTROL MEASURES AND FOR OBTAINING ALL REQUIRED PERMITS AND APPROVALS. ALL GRADING OPERATIONS SHALL BE SUSPENDED DURING SECOND (OR WORSE) STAGE SMOG ALERTS.

CONTACT INFO

OWNER:
CHABOT-LAS POSITAS COMMUNITY COLLEGE DISTRICT
CONTACT PERSON: ANN KROLL
3000 CAMPUS HILL DRIVE
LIVERMORE, CA 94551
E: AKROLL@CPCDD.ORG
PH: 510.514.1369

CIVIL ENGINEER:
SANDIS
CONTACT PERSON: BRIAN CANONILLA
636 9TH STREET
OAKLAND, CA 94607
E: BCANONILLA@SANDIS.NET
PH: 510.873.8866

PROJECT DESCRIPTION

THE PROJECT CONSISTS OF THE DEVELOPMENT OF A VACANT FIELD WITHIN THE NORTHEAST PORTION OF THE CAMPUS THAT HAS EXPERIENCED SIGNIFICANT STORMWATER PONDING AND HILLSIDE EROSION AS A RESULT OF THE RECENT STORM EVENTS. THE PROJECT WILL INSTALL A NEW STORM DRAIN CATCH BASIN AND PIPES CONVEYING RUNOFF TO THE BOTTOM OF THE SLOPE, RESTORE AND STABILIZE THE ERODED HILLSIDE AND REBUILD BENCHES AND GRAVEL PATHWAYS. THE DRAINAGE BASIN BELOW WILL BE PROTECTED USING ROCK SLOPE PROTECTION.

SHEET INDEX

- C0.0 COVER SHEET, CONSTRUCTION NOTES, AND ABBREVIATIONS
- C1.0 EXISTING CONDITIONS PLAN
- C2.0 HORIZONTAL CONTROL PLAN
- C3.0 GRADING AND DRAINAGE PLAN
- C3.1 ROUGH GRADING PLAN
- C3.2 CUT AND FILL MAP
- C4.0 CONSTRUCTION DETAILS
- C5.0 SEDIMENT AND EROSION CONTROL PLAN
- C5.1 SEDIMENT AND EROSION CONTROL PLAN



UNAUTHORIZED CHANGES AND USES

CAUTION: THE ENGINEER PREPARING THESE PLANS WILL NOT BE RESPONSIBLE FOR, OR LIABLE FOR, UNAUTHORIZED CHANGES TO OR USES OF THESE PLANS. ALL CHANGES TO THE PLANS MUST BE IN WRITING AND MUST BE APPROVED BY THE PREPARER OF THE PLANS.

CONSTRUCTION CONTRACTOR AGREES THAT IN ACCORDANCE WITH GENERALLY ACCEPTED CONSTRUCTION PRACTICES, CONSTRUCTION CONTRACTOR WILL BE REQUIRED TO ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THE PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY THAT THIS REQUIREMENT SHALL BE MADE TO APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS AND CONSTRUCTION CONTRACTOR FURTHER AGREES TO DEFEND, INDEMNIFY AND HOLD DESIGN PROFESSIONAL HARMLESS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT, EXCEPTING LIABILITY ARISING FROM SOLE NEGLIGENCE OF DESIGN PROFESSIONAL.



BUILD ON.
SANDIS.NET


DATE: 12-08-23

SCALE: N.T.S.

PROJECT No.: 618184

DATE: 12/11/2023

PROFESSIONAL SEAL: MICHAEL A. KUYENDALL, R.C.E. NO. 70870, EXPIRES 6-30-25



No.	REVISION	DATE	BY

LIVERMORE CALIFORNIA

HILLSIDE EROSION RESTORATION

COVER SHEET, CONSTRUCTION NOTES, AND ABBREVIATIONS


SHEET

C0.0

OF SHEETS

NO PART OF THIS DOCUMENT MAY BE REPRODUCED IN ANY FORM INCLUDING PHOTOCOPY, RECORDING OR ANY INFORMATION RETRIEVABLE AND STORAGE SYSTEM, WITHOUT PERMISSION IN WRITING FROM SANDIS.

NO PART OF THIS DOCUMENT MAY BE REPRODUCED IN ANY FORM INCLUDING PHOTOGRAPHY, RECORDING OR ANY INFORMATION RETRIEVABLE AND STORAGE SYSTEM, WITHOUT PERMISSION IN WRITING FROM SANDIS.



LEGEND

ALL DISTANCES AND DIMENSIONS ARE SHOWN IN FEET AND DECIMALS THEREOF.

- CURB LINE
- CONTOURS
- FENCE LINE, TYPE / HEIGHT AS INDICATED
- SPOT ELEVATION

SYMBOLS & ABBREVIATIONS

BFP		BACK FLOW PREVENTOR
BOL		BOLLARD
CNPT		CONTROL POINT
CONC		CONCRETE
CONC S/W		CONCRETE SIDEWALK
DD		DECK DRAIN
D		DRAIN INLET
EPB		ELECTRIC PULLBOX
PH		FIRE HYDRANT
G		GROUND
GB		GRADE BREAK
L/S		LANDSCAPE
MISC-CO		MISCELLANEOUS CLEANOUT
P		PAVEMENT
STL		STREET LIGHT LAMP NO ARM
WM		WATER METER
WV		WATER VALVE

SURVEY NOTES

- ALL DISTANCES AND DIMENSIONS ARE SHOWN IN FEET AND DECIMALS THEREOF.
- DATES OF FIELD SURVEY: 08/08/2023.
- HORIZONTAL AND VERTICAL CONTROL FOR THIS SURVEY ARE ON AN ASSUMED BASIS.

UNDERGROUND UTILITY NOTE

THE TYPES, LOCATIONS, SIZES AND/OR DEPTHS OF EXISTING UNDERGROUND UTILITIES AS SHOWN ON THIS TOPOGRAPHIC SURVEY ARE APPROXIMATE AND WERE OBTAINED FROM SOURCES OF VARYING RELIABILITY. ONLY ACTUAL EXCAVATION WILL REVEAL THE TYPES, EXTENT, SIZES, LOCATIONS AND DEPTHS OF SUCH UNDERGROUND UTILITIES. A REASONABLE EFFORT HAS BEEN MADE TO LOCATE AND DELINEATE ALL KNOWN UNDERGROUND UTILITIES. HOWEVER, THE ENGINEER CAN ASSUME NO RESPONSIBILITY FOR THE COMPLETENESS OR ACCURACY OF ITS DELINEATION OF SUCH UNDERGROUND UTILITIES WHICH MAY BE ENCOUNTERED, BUT WHICH ARE NOT SHOWN ON THIS SURVEY.



BUILD ON.
SANDIS.NET

DATE: 12-08-23
SCALE: 1"=10'
PROJECT No.: 618184

DATE: 12/11/2023
MICHAEL A. KUYKENDALL
R.C.E. NO. 70870, EXPIRES 6-30-25
CIVIL ENGINEER
STATE OF CALIFORNIA

No.	REVISION	DATE	BY

HILLSIDE EROSION RESTORATION


LIVERMORE

CALIFORNIA

EXISTING CONDITIONS PLAN

SHEET
C1.0
OF SHEETS

NO PART OF THIS DOCUMENT MAY BE REPRODUCED IN ANY FORM INCLUDING PHOTOGRAPHY, RECORDING OR ANY INFORMATION RETRIEVABLE AND STORAGE SYSTEM, WITHOUT PERMISSION IN WRITING FROM SANDIS.



- LEGEND**
- APPROXIMATE LIMIT OF WORK
 - EXTENT OF TRENCH BACKFILL/HILLSIDE RESTORATION
 - STORM DRAIN PIPE (HOPE TYPE 5)
 - GRAVEL ROAD (3/4.0)
 - TRENCH BACKFILL/HILLSIDE RESTORATION (1/4.0)
 - RIP RAP (4/4.0)

ALIGNMENT SECTIONS

LINE TABLE		
LINE	BEARING	LENGTH
L1	S68°18'42"E	209.83'
L2	S45°52'09"E	100.17'



PROJECT CONTROL
1"=30'



BUILD ON
SANDIS.NET

DATE: 12-08-23
SCALE: 1"=10'
PROJECT No.: 618184

DATE: 12/11/2023
MICHAEL A. KOPKENDALL
R.C.E. NO. 70870, EXPIRES 6-30-25

No.	REVISION	DATE	BY

HILLSIDE EROSION RESTORATION


LIVERMORE

CALIFORNIA

HORIZONTAL CONTROL PLAN

SHEET
C2.0
OF SHEETS




NO PART OF THIS DOCUMENT MAY BE REPRODUCED IN ANY FORM INCLUDING PHOTOGRAPHY, RECORDING OR ANY INFORMATION RETRIEVABLE AND STORAGE SYSTEM, WITHOUT PERMISSION IN WRITING FROM SANDS.



LEGEND

- APPROXIMATE LIMIT OF WORK
- - - EXTENT OF TRENCH BACKFILL/HILLSIDE RESTORATION
- ▬ STORM DRAIN PIPE (HDPE TYPE S)
- ⊕⊕⊕⊕⊕ GRAVEL ROAD
- ▭ TRENCH BACKFILL/HILLSIDE RESTORATION
- ▭ RIP RAP

- ### EARTHWORK NOTES
- OVER EXCAVATE ERODED CHANNEL AND CONSTRUCT BENCH CONDITION PER DETAIL 1 ON SHEET C4.0. BACKFILL WITH APPROVED ON-SITE MATERIAL IN LIFTS NOT EXCEEDING 8 INCHES IN THICKNESS AND COMPACTED TO AT LEAST 90% RELATIVE COMPACTION. TILL SECTIONS GREATER THAN 5 FEET IN DEPTH SHALL BE COMPACTED TO AT LEAST 95% RELATIVE COMPACTION.
 - FILL MATERIAL SHALL BE FREE OF ROCKS OR LUMPS IN EXCESS OF 6 INCHES IN DIAMETER, TRASH, DEBRIS, VEGETATION OR OTHER DELETERIOUS MATERIAL. SHALL CONTAIN LESS THAN 3 PERCENT ORGANIC CONTENT BY DRY WEIGHT.
 - THE PROJECT IS A BALANCED CONDITION AND THE FILL MATERIAL SHALL BE SOURCED FROM CUT GENERATED FROM ROUGH GRADING EFFORT SHOWN ON SHEET C3.1. CONTRACTOR SHALL SAMPLE STOCK PILE MATERIAL PRIOR USE TO CONFIRM SUITABILITY.
 - ANY MATERIAL EXCAVATED BY THE PROJECT WHICH IS UNSUITABLE FOR USE AS FILL SHALL BE DISPOSED OF ON-SITE. CONTRACTOR TO COORDINATE WITH DISTRICT REPRESENTATIVE FOR SPECIFIC LOCATION.
 - FIELD QUALITY CONTROL TO BE DONE BY FIELD OBSERVATIONS AND IN-PLACE DENSITY TEST PERFORMED BY THE DISTRICT'S TESTING AGENCY. FIELD TEST SHALL BE AT FREQUENCY NO LESS THAN EVERY LIFT AND EVERY 100 CUBIC YARDS PLACED. CONTRACTOR TO PROVIDE PROPOSED SOURCE OF WORK TO THE DISTRICT'S REPRESENTATIVE FOR COORDINATION OF FIELD TESTING.
 - WHEN TESTING AGENCY REPORTS THAT SUBGRADES, FILLS OR BACKFILLS ARE BELOW SPECIFIED DENSITY, CONTRACTOR SHALL REMEDY THE WORK BY SCARIFY AND MOISTEN OR AERATE, OR REMOVE AND REPLACE SOIL TO THE DEPTH REQUIRED, AND RE-COMPACT AND RE-TEST UNTIL REQUIRED DENSITY IS OBTAINED. CONTRACTOR IS RESPONSIBLE THE COST OF THE REWORK AND RE-TESTING.
 - CONTRACTOR TO PROVIDE REPRESENTATIVE SAMPLES OF FILL MATERIAL TO OWNER'S TESTING AGENCY FOR ANALYSIS AND DEVELOPMENT OF COMPACTION CURVE.



- ### STORM DRAINAGE NOTES
- ALL PIPE MATERIALS AND FITTINGS SHALL HOPE CONFORMING TO AASHTO M294 TYPE S.
 - PIPES SHALL BE BEDDED IN TRENCH SAND. TRENCH SAND SHALL BE FREE OF CLAY, ORGANIC MATERIALS AND OTHER DELETERIOUS SUBSTANCES AND CONFORMING TO CALTRANS STANDARD SPECIFICATION SECTION 19-3.02(2).
 - THOROUGHLY CLEAN STORM DRAIN LINES AND FIELD INLETS OF DIRT, DEBRIS, AND OBSTRUCTIONS OF ANY KIND.
 - AFTER COMPLETION OF PIPE INSTALLATION, INCLUDING COMPACTION TO FINISH GRADE, PERFORM VIDEO INSPECTION OF THE PIPE TO CONFIRM IT IS FREE OF DEFECTS. DEFECTS WOULD INCLUDE GAPS IN JOINTS, OBSTRUCTIONS TO THE PIPELINE, OR DEFLECTION OF PIPE WALLS. VIDEOS SHALL INCLUDE INDICATION OF DISTANCE ALONG PIPE, AND BE TAKEN WITH A CAMERA WITH PAN AND TILT CAPABILITIES.
 - ANY IDENTIFIED DEFECTS SHALL BE REPAIRED BY THE CONTRACTOR AT THE CONTRACTOR'S COST.

WORK DESCRIPTION

INTENT IS TO OVEREXCAVATE ERODED CHANNEL, INSTALL STORM DRAIN LINE, AND RE-ESTABLISH HILLSIDE WITH NATIVE SOIL. IF FILL IS NEEDED, IT SHALL BE SOURCED FROM CUT GENERATED FROM ROUGH GRADING EFFORT. SEE SHEET C3.1.

SCALES:
1"=10' HORIZ
1"=10' VERT.



BUILD ON.
SANDIS.NET

DATE: 12-08-23
SCALE: 1"=10'
PROJECT No.: 618184
DATE: 12/11/2023
MICHAEL A. KUKKENDALL
R.C.E. No. 70870, EXPIRES 6-30-25


No.	REVISION	DATE	BY

HILLSIDE EROSION RESTORATION
LIVERMORE CALIFORNIA

GRADING AND DRAINAGE PLAN

SHEET
C3.0
OF SHEETS

NO PART OF THIS DOCUMENT MAY BE REPRODUCED IN ANY FORM INCLUDING PHOTOCOPY, RECORDING OR ANY INFORMATION RETRIEVABLE AND STORAGE SYSTEM, WITHOUT PERMISSION IN WRITING FROM SANDIS.



LEGEND

- APPROXIMATE LIMIT OF WORK
- EXTENT OF TRENCH BACKFILL/HILLSIDE RESTORATION
- FLOWLINE
- STORM DRAIN PIPE (HDPE TYPE S)
- GRAVEL ROAD
- TRENCH BACKFILL/HILLSIDE RESTORATION
- RIP RAP
- REGRADED SOIL AREA

WORK DESCRIPTION
 INTENT IS TO GRADE THE AREA TO GENERATE POSITIVE DRAINAGE TO PROPOSED CATCH BASIN. ANY REQUIRED FILL SHALL BE PROVIDED BY CUT GENERATED FROM GRADING WORK IN THE IMMEDIATE VICINITY. CONTRACTOR TO DISCUSS DIFFERENCES IN FIELD CONDITIONS WITH ENGINEER IF ANY EXIST.

ADD ALTERNATE DESCRIPTION
 UPON DEMOBILIZATION AND CONSTRUCTION FENCE REMOVAL OF THE VITICULTURE BUILDING PROJECT, REGRADE AREA TO PROVIDE POSITIVE DRAINAGE TOWARDS PROPOSED DRAINAGE INLET.



BUILD ON.
SANDIS.NET

DATE: 12-08-23
 SCALE: 1"=30'
 PROJECT No.: 618184
 DATE: 12/11
 MICHAEL A. KUYKENDALL
 R.C.E. NO. 70870, EXPIRES 6-30-25
 CIVIL ENGINEER
 STATE OF CALIFORNIA

No.	REVISION	DATE	BY


HILLSIDE EROSION RESTORATION
 LIVERMORE CALIFORNIA

ROUGH GRADING PLAN
 SHEET C3.1
 OF SHEETS

File: X:\P\618184\HILLSIDE EROSION RESTORATION PROJECT\4-ENGINEERING\2-PLAN SETS\3-SHEET SET\ONSITE\C3.1 ROUGH GRADING PLAN.dwg Date: Dec 11, 2023 - 9:46 AM

Copyright ©2023 by Sandis

NO PART OF THIS DOCUMENT MAY BE REPRODUCED IN ANY FORM INCLUDING PHOTOGRAPHY, RECORDING OR ANY INFORMATION RETRIEVABLE AND STORAGE SYSTEM, WITHOUT PERMISSION IN WRITING FROM SANDIS.



LEGEND

	AREA OF CUT
	AREA OF FILL
-0.1	DEPTH OF CUT
+0.1	DEPTH OF FILL

ADD ALTERNATE (SEE SHEET C3.1)



BUILD ON.
SANDIS.NET

DATE: 12-08-23
SCALE: 1"=30'
PROJECT No.: 618184

DATE: 12/11
MICHAEL A. KUYKENDALL
R.C.E. NO. 70870, EXPIRES 6-30-25
CIVIL ENGINEER
STATE OF CALIFORNIA

No.	REVISION	DATE	BY


HILLSIDE EROSION RESTORATION
LIVERMORE CALIFORNIA

CUT AND FILL MAP

SHEET
C3.2
OF SHEETS


File: X:\P\618184\HILLSIDE EROSION RESTORATION PROJECT\4_ENGINEERING\2_PLAN SETS\3_SHEET SET\ONSITE\C3.2 CUT AND FILL MAP.dwg Date: Dec 11, 2023 - 9:48 AM

Copyright ©2023 by Sandis




- CONSTRUCTION NOTES:**
- ADDITIONAL BACKFILL MATERIAL TO BE COLLECTED FROM NATIVE SOIL STOCK PILE ADJACENT TO HORTICULTURE FACILITY.

TYPICAL TRENCH SECTION 1
N.T.S.




- CONSTRUCTION NOTES:**
- REFER TO DESIGN PLANS FOR TRENCH DAM LOCATIONS.
 - CONTROLLED LOW STRENGTH MATERIAL FILL SHALL BE 50 - 100 PSI STRENGTH WITH A WATER CONDUCTIVITY OF 1.0×10^{-4} CM/SEC (MAX).
 - TRENCH DAM SHALL EXTEND BEYOND THE TOE OF TRENCH INTO THE NATIVE SOIL PER THE MINIMUM DIMENSIONS SHOWN. THE TRENCH DAM SHALL HAVE A MINIMUM THICKNESS OF 1" (MEASURED PARALLEL TO THE UTILITY PIPE LENGTH).
 - ADDITIONAL BACKFILL MATERIAL TO BE COLLECTED FROM NATIVE SOIL STOCK PILE ADJACENT TO HORTICULTURE FACILITY.

CLSM TRENCH DAM 2
N.T.S.




GRAVEL ROAD SECTION 3
1"=1'




- NOTES:**
- SEE DETAIL 6 FOR CATCH BASIN SIZE AND TYPE.
 - FRAME SHALL BE ANCHORED TO CONCRETE PER MANUFACTURER'S SPECIFICATIONS.
 - FOR JUNCTION BOXES (JB) IN NON-VEHICULAR AREAS ONLY, REPLACE GRATE WITH NON-SLIP SOLID STEEL COVER. ADD "STORM DRAIN" TEXT TO LID.

CATCH BASIN TOP 5
1"=1'




- NOTES:**
- SEE PLANS FOR DRAIN INLET SIZE.
 - PRE-CAST DRAIN INLET IN LIEU OF CAST-IN-PLACE INLET IS ACCEPTABLE. OLDCASTLE OR APPROVED EQUIVALENT.

DRAIN INLET BASE 6
1"=1'



SD OUTFALL 7
N.T.S.



RIP-RAP LAYOUT 4
N.T.S.



BUILD ON.
SANDIS.NET

DATE: 12-08-23
SCALE: 1"=20'
PROJECT No.:
618184

DATE: 12/11/2023
MICHAEL A. KOPKENDALL
R.C.E. NO. 70870, EXPIRES 6-30-25

No.	REVISION	DATE	BY

HILLSIDE EROSION RESTORATION

LIVERMORE


CALIFORNIA

CONSTRUCTION DETAILS

SHEET
C4.0

OF SHEETS

NO PART OF THIS DOCUMENT MAY BE REPRODUCED IN ANY FORM INCLUDING PHOTOCOPY, RECORDING OR ANY INFORMATION RETRIEVABLE AND STORAGE SYSTEM, WITHOUT PERMISSION IN WRITING FROM SANDIS.






LEGEND

- HYDROSEED PLANTING (SEE NOTES)
- FIBER ROLL (1 C5.0)
- INLET PROTECTION (2&3 C5.0)
- APPROXIMATE AREA OF CONSTRUCTION DISTURBANCE - AREA TO COMPLY WITH REQUIREMENTS IN PROJECT SWPPP
- STABILIZED ENTRANCE/EXIT

- ### WATER POLLUTION CONTROL NOTES:
- A. TEMPORARY CONSTRUCTION ENTRANCE/EXIT LOCATION SHOWN IS APPROXIMATE. CONTRACTOR TO PROVIDE LOCATION WHERE APPROPRIATE.
 - B. THIS PLAN REPRESENTS POSSIBLE WATER POLLUTION CONTROL MEASURES INCLUDING EROSION CONTROL AND SEDIMENT CONTROL.
 - C. EXISTING SURFACES SHALL BE UNDISTURBED TO THE EXTENT PRACTICAL.
 - D. GROUND WATER SHALL NOT BE DISCHARGED WITH STORM WATER. GROUND WATER DEWATERING OPERATIONS SHALL BE COORDINATED AS NEEDED WITH OWNER.
 - E. CONTRACTOR SHALL PROVIDE EFFECTIVE SOIL COVER FOR AREAS OF CONSTRUCTION ACTIVITY THAT HAVE BEEN DISTURBED AND ARE NOT SCHEDULED TO BE ACTIVE FOR AT LEAST 14 DAYS.
 - F. ALL EROSION CONTROL AND SEDIMENT CONTROLS TO BE OBTAINED INSTALLED AND MAINTAINED AS REQUIRED IN PROJECT SWPPP.
 - G. CONTRACTOR TO INSTALL RUN-ON AND RUN-OFF CONTROL MEASURES ACCORDING TO PLANS OR AS NECESSARY TO ENSURE SEDIMENT IS NOT TRANSPORTED FROM SITE.
 - H. CONTRACTOR TO PROVIDE BACK-UP EROSION PREVENTION MEASURES (SOIL STABILIZATION) WITH SEDIMENT CONTROL MEASURES SUCH AS STRAW WATTLES, SILT FENCE, GRAVEL INLET FILTERS, AND/OR SEDIMENT TRAPS OR BASINS. ENSURE CONTROL MEASURES ARE ADEQUATE, IN PLACE, AND IN OPERABLE CONDITIONS. SEDIMENT CONTROLS, INCLUDING INLET PROTECTION, ARE NECESSARY BUT SHOULD BE A SECONDARY DEFENSE BEHIND GOOD EROSION CONTROL MEASURES.
 - I. STOCKPILE LOCATION(S) TO BE DETERMINED BY THE CONTRACTOR. COORDINATE WITH SITE OSP.
 - J. ALL CONCRETE TRUCKS TO USE CHUTE WASH BUCKETS FOR CONCRETE RINSE. ALL CONCRETE PUMPS TO CAPTURE CONCRETE RINSE IN SECONDARY CONTAINMENT AND PROPERLY DISPOSE.
 - K. STREET SWEEPING SHALL BE CHECKED DAILY TO ENSURE DEPOSITED SEDIMENT AND DEBRIS DOES NOT ENTER THE STORM DRAIN SYSTEM. USE REGENERATIVE VACUUM STREET CLEANER TO MITIGATE AIR AND WATER POLLUTION.
 - L. RUNOFF THAT HAS CONTACTED AMENDED SOIL AREAS SHALL NOT BE ALLOWED TO LEAVE THE SITE OR ENTER THE STORM DRAIN SYSTEM.

- ### HYDROSEED NOTES
1. CALTRANS PERGRASS SHALL BE USED AS HYDROSEED MIX TYPE.
 2. IF PLANTED OUTSIDE OF RAINY SEASON, CONTRACTOR TO PROVIDE IRRIGATION PER MANUFACTURER RECOMMENDATIONS UNTIL VEGETATION IS ESTABLISHED.

NO PART OF THIS DOCUMENT MAY BE REPRODUCED IN ANY FORM INCLUDING PHOTOGRAPHY, RECORDING OR ANY INFORMATION RETRIEVABLE AND STORAGE SYSTEM, WITHOUT PERMISSION IN WRITING FROM SANDIS.



SANDIS

BUILD ON SANDIS.NET

DATE: 12-08-23	DATE: 12/11/2023		No.	REVISION	DATE	BY
SCALE: 1"=10'						
PROJECT No.: 618184	MICHAEL A. KUYKENDALL R.C.E. NO. 70870, EXPIRES 6-30-25					


HILLSIDE EROSION RESTORATION

LIVERMORE CALIFORNIA






SEDIMENT AND EROSION CONTROL PLAN

SHEET C5.0 OF SHEETS

NO PART OF THIS DOCUMENT MAY BE REPRODUCED IN ANY FORM INCLUDING PHOTOGRAPHY, RECORDING OR ANY INFORMATION RETRIEVABLE AND STORAGE SYSTEM, WITHOUT PERMISSION IN WRITING FROM SANDIS.



LEGEND

-  HYDROSEED PLANTING (SEE NOTES)
-  FIBER ROLL 1
C5.1
-  INLET PROTECTION 2&3
C5.1
-  APPROXIMATE AREA OF CONSTRUCTION DISTURBANCE - AREA TO COMPLY WITH REQUIREMENTS IN PROJECT SWPPP
-  STABILIZED ENTRANCE/EXIT

WATER POLLUTION CONTROL NOTES:

- A. TEMPORARY CONSTRUCTION ENTRANCE/EXIT LOCATION SHOWN IS APPROXIMATE. CONTRACTOR TO PROVIDE LOCATION WHERE APPROPRIATE.
- B. THIS PLAN REPRESENTS POSSIBLE WATER POLLUTION CONTROL MEASURES INCLUDING EROSION CONTROL AND SEDIMENT CONTROL.
- C. EXISTING SURFACES SHALL BE UNDISTURBED TO THE EXTENT PRACTICAL.
- D. GROUND WATER SHALL NOT BE DISCHARGED WITH STORM WATER. GROUND WATER DEWATERING OPERATIONS SHALL BE COORDINATED AS NEEDED WITH OWNER.
- E. CONTRACTOR SHALL PROVIDE EFFECTIVE SOIL COVER FOR AREAS OF CONSTRUCTION ACTIVITY THAT HAVE BEEN DISTURBED AND ARE NOT SCHEDULED TO BE ACTIVE FOR AT LEAST 14 DAYS.
- F. ALL EROSION CONTROL AND SEDIMENT CONTROLS TO BE OBTAINED INSTALLED AND MAINTAINED AS REQUIRED IN PROJECT SWPPP.
- G. CONTRACTOR TO INSTALL RUN-ON AND RUN-OFF CONTROL MEASURES ACCORDING TO PLANS OR AS NECESSARY TO ENSURE SEDIMENT IS NOT TRANSPORTED FROM SITE.
- H. CONTRACTOR TO PROVIDE BACK-UP EROSION PREVENTION MEASURES (SOIL STABILIZATION) WITH SEDIMENT CONTROL MEASURES SUCH AS STRAW WATTLES, SILT FENCE, GRAVEL INLET FILTERS, AND/OR SEDIMENT TRAPS OR BASINS. ENSURE CONTROL MEASURES ARE ADEQUATE, IN PLACE, AND IN OPERABLE CONDITIONS. SEDIMENT CONTROLS, INCLUDING INLET PROTECTION, ARE NECESSARY BUT SHOULD BE A SECONDARY DEFENSE BEHIND GOOD EROSION CONTROL MEASURES.
- I. STOCKPILE LOCATION(S) TO BE DETERMINED BY THE CONTRACTOR. COORDINATE WITH SITE O&P.
- J. ALL CONCRETE TRUCKS TO USE CHUTE WASH BUCKETS FOR CONCRETE RINSE, ALL CONCRETE PUMPS TO CAPTURE CONCRETE RINSE IN SECONDARY CONTAINMENT AND PROPERLY DISPOSE.
- K. STREET SWEEPING SHALL BE CHECKED DAILY TO ENSURE DEPOSITED SEDIMENT AND DEBRIS DOES NOT ENTER THE STORM DRAIN SYSTEM. USE REGENERATIVE VACUUM STREET CLEANER TO MITIGATE AIR AND WATER POLLUTION.
- L. RUNOFF THAT HAS CONTACTED AMENDED SOIL AREAS SHALL NOT BE ALLOWED TO LEAVE THE SITE OR ENTER THE STORM DRAIN SYSTEM.

HYDROSEED NOTES

1. CALTRANS PERGRASS SHALL BE USED AS HYDROSEED MIX TYPE.
2. IF PLANTED OUTSIDE OF RAINY SEASON, CONTRACTOR TO PROVIDE IRRIGATION PER MANUFACTURER RECOMMENDATIONS UNTIL VEGETATION IS ESTABLISHED.



BUILD ON
SANDIS.NET

DATE: 12-08-23
SCALE: 1"=10'
PROJECT No.: 618184

DATE: 12/11/2023
MICHAEL A. KUYKENDALL
R.C.E. NO. 70870, EXPIRES 6-30-25
CIVIL ENGINEER
STATE OF CALIFORNIA

No.	REVISION	DATE	BY

HILLSIDE EROSION RESTORATION
LIVERMORE CALIFORNIA

SEDIMENT AND EROSION CONTROL PLAN

SHEET
C5.1
OF SHEETS